



Techniczne aspekty LHC
(*Large Hadron Collider*)


Jan Kulka

27-02-2009




- - Zespół akceleratorów wokół LHC
- - Podstawowe systemy LHC oraz udział WFiIS AGH w uruchomieniu
 - Magnesy dipolowe i kwadrupolowe
 - Obwody kriogeniczne
 - Systemy ochrony magnesów i systemy ekstrakcji energii
 - Klimatyzacja i wentylacja
- - Uruchomienie LHC
- - Awarie
- - Perspektywy

CERN Accelerator Complex



▶ p (proton) ▶ ion ▶ neutrons ▶ $\bar{p}$ (antiproton) ▶ neutrinos ▶ electron
 ↔↔↔ proton/antiproton conversion

LHC Large Hadron Collider SPS Super Proton Synchrotron PS Proton Synchrotron
 AD Antiproton Decelerator CTF3 Clic Test Facility
 CNGS Cern Neutrinos to Gran Sasso ISOLDE Isotope Separator OnLine DEvice
 LEIR Low Energy Ion Ring LINAC LINEar ACcelerator n-ToF Neutrons Time Of Flight



	<u>Top energy(GeV)</u>	
	<u>Circumference(m)</u>	
LINAC2	0.12	30
PSB	1.4	157
CPS	26	628 = 4 PSB
SPS	450	6911 = 11 x PS
LHC	7000	26657 = 27/7xSPS

Ważniejsze daty LHC

1982 : Pierwsze prace
studialne nad LHC

1994 : Zatwierdzenie LHC
przez CERN Council

1996 : Ostateczna decyzja o
konstrukcji LHC (7TeV)

2003 : Rozpoczęcie
instalacji LHC

2006 : Rozpoczęcie
odbioru technicznego

2007 : Zakończenie
instalacji i start
chłodzenia


← 1984 : Rozpoczęcie
budowy LEP

← 1989 : Uruchomienie
LEP


← 1995 : Rozpoczęcie prac
przy budowie hal
eksperymentów LHC

← 2000 : Koniec działania
LEP

Magnes dipolowy, jeden z 1232 w LHC, temp. pracy 1,9K




Magnesy dipolowe LHC




- Energia każdej paczki protonów- 7TeV $\Leftrightarrow$
Indukcja w dipolu
8.33T



(Btot)(T)





Indukcja magnetyczna w dwu-aperturowym dipolu

















Critical current density of technical superconductors



Specific heat of LHe and Cu




Equivalent thermal conductivity of He II






Phase diagram of Helium




Linear heat exchanger

LHC magnet string cooling scheme



Przekrój dipola LHC




Kompozytowa noga magnesu

G10 Glass-fibre Reinforced Epoxy



Blokada dopływu ciepła



Zasilanie ciekłym
helem 4,5K (linia C')

Płyty aluminiowe
klejone do nogi
kompozytu G-10

Łączniki do łoża
aluminiowego ekranu
termicznego 50-75 K

Aluminiowe łożo magnesu wspornikiem ekranu termicznego



Izolacja aluminiowa zimnej masy



Wielowarstwowy koc izolacji termicznej (MLI)



Kriostaty próżniowe

Stal nierdzewna, 1000 mm, 1000 mm, 1000 mm



Skład osobowy pracowników AGH pracujących przy uruchomieniu LHC w okresie 2005-2009

MEL

Bednarek	Mateusz
Ludwin	Jaromir
Prochal	Bogusław
Setkowicz	Józef

QP

Drózd	Adam
Filipek	Wiesław
Gorzawski	Arkadiusz
Nowak	Edward
Nowak	Elżbieta
Seweryn	Grzegorz
Skala	Aleksander
Skoczeń	Andrzej
Wojanek	Piotr

QRL

Bolewski	Andrzej
Ciechanowski	Marek
Donizak	Jędrzej
Dubert	Paweł
Fluder	Czesław
Gaj	Wawrzyniec
Jodłowski	Paweł
Klisch	Michał
Macuda	Paweł
Malinowski	Paweł
Palica	Jan
Skotnicki	Ryszard
Sosin	Mateusz
Wróbel	Bartłomiej
Zwaliński	Łukasz
Lis	Krzysztof
Wolak	Tomasz

TS

Macuda	Małgorzata
Szkutnik	Jacek

TS/CV

Baran	Krzysztof
Dubert	Anna
Pomocka	Marek
Urbaniec	Bartłomiej
Wiencek	Mateusz


CRJ

Kulka	Jan
-------	-----


Linia dystrybucyjna ciekłego helu o długości 3,3km





Elementy systemu kriogenicznego



Przepływy helowe w komórce kriogenicznej LHC



indukcija




$$B_y = \frac{\mu_0 J b d}{a + b}$$


$$B_x = \frac{\mu, J(a - b)}{a + b} y$$

$$B_y = \frac{\mu, J(a - b)}{a + b} x$$

<i>Kryterium selekcji</i>	<i>Liczba</i>
Nadprzewodnik	$\sim 10,000$
$T_c \cong 10 \text{ K}$.and. $B_{c2} \cong 10 \text{ T}$	~ 100
$J_c \cong 1 \text{ GA/m}^2 @ B > 5 \text{ T}$	~ 10
Magnet-grade superconductor	~ 1




Niob-Tytan




Critical surface of NbTi (from Wilson textbook)

Critical current density vs field measured on NbTi multifilamentary wire at 4.22 and 2.17 K





Critical current of best Cu/NbTi with typical **3 T field shift at superfluid helium** (INFN-LASA lab, february 2000)






Grzejnik quenchowy




Ekran wiązki




3D Cewka strona liry




Strona podłączeniowa cewki




Jarzmo stalowe dipola




Płyta kończąca dipola




Formowanie liry




Korpus ciśnieniowy zimnej masy




Wymiennik ciepła




Magnesy korekcyjne dipola (spool pieces)




Zamknięcie zimnej masy dipola dennicą




Dennica dipola i pozycjonowanie (Cold feet)



Mieszki kompensacyjne + linia N



Energy stored in LHC magnets




$$E_{\text{dipole}} = 0.5 \cdot L_{\text{dipole}} \cdot I_{\text{dipole}}^2$$

Energy stored in one dipole is 7.6 MJoule

For all 1232 dipoles in the LHC: 9.4 GJ

Energy stored in the beams



Beam energy: Proton Energy • Number of Bunches • Number of protons per bunch

Proton Energy: 7 TeV


In order to achieve very high luminosity:


Number of bunches per beam: 2808

Number of protons per bunch: $1.05 \cdot 10^{11}$


Energy per beam: 346 MJoule

Schemat zrzućania wiązki






Temperatura w bloku grafitu - 80 cm



- Schematics of the QPS in the main dipoles of a sector



If not fast and safe ...




During magnet test campaign, the 7 MJ stored in one magnet were released into one spot of the coil (inter-turn short)

P. Pognat

III.II Momentum and betatron


MOMENTUM CLEANING INSERTION

(collimators are not shown)



BETATRON CLEANING INSERTION

(collimators are not shown)



Particles with large momentum offset are scattered by the primary collimators in IR3.


Particles with large H, V or H&V betatron amplitudes are scattered by the primary collimators in IR7.


In both cases the scattered particles are absorbed by secondary collimators.

Typical quadrupole strength 30-35 T/m


Note: IR3 & IR7 have special DS (arc quadrupoles in series + trim quadrupoles) because of lack of space to place the power converters.

III.II Momentum and betatron cleaning insertions (IR3, IR7)






Injection Test 1




Injection Test 1

- Achieved
 - Synchronization SPS – LHC
 - **Beam 1** injected IP2
 - Through to collimators in IP3 first shot →
 - Trajectory correction
 - Kick-response measurements
 - Off-energy measurements (dispersion)
 - Explored the aperture
 - First beam induced quench
- Discovered
 - Aperture restriction in the injection line
 - Traced to misaligned vacuum pump
 - Optics problem IP3
 - Polarity convention QTL



Injection Test 2






Injection Test 2

- Achieved


- Beam 2 injected IP8
- Through to collimators in IP7 first shot
- Trajectory correction
- Kick-response measurements
- Off-energy measurements (dispersion)
- Explored the aperture
- Beam 1 injected IP2
- Through to collimators in IP3
- Aperture in injection region OK
- Polarity correction confirmed
- Interleaved injection

- Discovered

- Optics problem at the end of the TI8 line




Injection Test 3




Injection Test 3

- Achieved
 - Beam 2 injected IP8
 - Threaded to dump in IP6
 - Steered then inject and dump
 - Beam 1 injected IP2
 - Threaded through to coll in IP5
- Discovered
 - Optics problem in IP7
 - Polarity convention on Q6
 - Optics problem in IP4
 - Polarity convention




10th of September



10th of September



- Achieved
 - Beam 1 injected IP2
 - Threaded around the machine in 1h
 - Trajectory steering gave 2 or 3 turns
- Beam 2 injected IP8
- Threaded around the machine in 1h30
- Trajectory steering gave 2 or 3 turns
- Q and Q' trims gave a few hundred turns

10th of September Beam 1 – First turn trajectory




10th of September

Beam 1 on TDI screen – 1st and 2nd turns




10th of September

Beam 2 – First turn trajectory




14.14.10 01 September

Beam 2: Longitudinal Bunch Profile




IV.IV. 10th of September

Beam 2 closed orbit




IV.IV. 10th of September




Beam 2 fast BCT (Beam Current Transformer)



Intensity $\sim 3 \cdot 10^9$




10th of September Beam dilution on dump block



10th of September

Beam 2 captured – mountain range display

Turn number



Bunch length

Now RF ON

10th of September



HTS in the LHC machine



Powering of the LHC magnets

About 3 MA of rated current for
1800 circuits

3286 current leads

Quantity	Current rating (A)
64	13000
298	6000
820	600
2104	60-120


HTS




Superconducting Magnets Summer
2006 Tom Taylor



DFBAO in Sector 7-8



RF cavities



Two 300 kW klystrons with circulators and loads



Construction and commissioning 2002-2008

Tunnel activity determined by

Triplet

2002

2003


2004

2005

2006

2007

2008




Inner Triplets
Either side of each experiment
Provide focusing at the Interaction




Construction and commissioning 2002-2008

Tunnel activity determined by




During the pressure test of Sector 7-8 (25 November 2006) the corrugated heat exchanger tube in the inner triplet failed by buckling at 9 bar (external) differential pressure



On Tuesday March 27 2007 there was a serious failure in a high-pressure test at CERN of a Fermilab-built inner-triplet series of three quadrupole magnets left of Point 5

Construction and commissioning 2002-2008


Tunnel activity determined by



Redesign of the heat exchanger:
new Cu tubes with larger buckling
pressure, and new bi-metallic
transitions in the ends.



Redesign of the support system
based on four cartridges that
react to the longitudinal forces
and retain the fixed point of the
cold mass in its original position



**Both repairs had
to be made on all 8
triplet assemblies**

**Some were
already installed
in the machine**

Construction and commissioning 2002-2008

Tunnel activity determined by

Triplet

2002

2003

2004

2005

2006

2007

2008

QQBI.26R7 line V2

The PiM problem

-- Innovation --

Light ball transmitting at 40MHz
Blown through an LHC arc
Detected by Beam Position Monitors


Stopped by buckled PiMs



Arc plug-in module at working temperature




Arc plug-in module




Incident of September 19th 2008

- During a few days period without beam
- Making the last step of dipole circuit in sector 34, to 9.3kA
- At 8.7kA, **development of resistive zone in the dipole bus bar splice** between Q24 R3 and the neighbouring dipole
- Electrical arc developed which punctured the helium enclosure
- **Helium released into the insulating vacuum**
- Rapid pressure rise inside the LHC magnets
 - Large pressure wave travelled along the accelerator both ways
 - Self actuating relief valves opened but could not handle all
 - Large forces exerted on the vacuum barriers located every 2 cells
 - These forces displaced several quadrupoles and dipoles
 - Connections to the cryogenic line affected in some places
 - Beam vacuum also affected


Development of resistive zone in dipole bus bar splice



Bus bar splice




Working hypothesis



Favored *hypothesis* for the S34 incident cause :


- Temperature increase due to excessive resistance (estimate $\sim 200\text{n}\Omega$)
- Superconductor quenches and becomes resistive at high current
- Up to a certain current, the copper can take it (cooled by the He II)
- Beyond a certain current, 'run-away' of the temperature, splice opens, electrical arc ...

Helium released into the




Liquid
to
Gas
Expansion
Factor

1000




Consequences



- Considerable collateral damage over few hundred metres
- Insulating vacuum barrier every 2 cells in the arc → Some moved
- Damage to superinsulation blankets
- Contamination (by soot and insulation blankets) of beam pipes
- Large release of helium into the tunnel (6 of 15 tonnes)

Consequences




What is it (for) ?

Construction

Beam

Breakdown

Repair



- Present strategy assumes treating all magnets Q19 to Q33 as shown
- 53 have to be brought to the surface (39 dipoles and 14 quads)
- Will be replaced with spare / refitted, retested and reinstalled
- Estimate for magnets November 08 to March 09
- Not forgetting cleaning the beam pipes
- Then have to finish interconnection, cool down, power test

Post Mortem (needles and haystacks)


- Following the incident, a close look at the logged cryogenic data (temperatures and valve states) indicated **abnormal behaviour** in the cell that was at the origin of the fault **mK**
- This was followed by systematic scrutiny of all data logged during the weeks of power testing of all 8 sectors
- **Anomalous cryogenic behaviour** found in sector 12 at 7kA
 - Higher than nominal **heat load** in cryogenic sector 15 R1 **W**
- Confirmed by detailed tests in late 2008
- Corresponding **electrical resistance** calculated **0.3nΩ**
- **No other faulty splice has been found** **!**
- Electrical measurements located it to **inside** a dipole **90nΩ**
!
100nΩ
47nΩ

R.Bailey, Aspen 2009

- Another resistance found **inside** a dipole in sector 67

Protection

- These investigations have led to the development of **powerful calorimetric and electric methods** to detect excessive resistances in the main LHC magnet circuits
- These methods have been prototyped and will be further improved before being installed machine-wide and applied as **dedicated procedures** during the machine commissioning



**2000 new electronic crates
160km of cable to be pulled**

Further measures

- Mitigate the consequences of any event similar to that in sector 34 by increasing the helium gas release capability
- All quadrupole cryostats have spare flanges
 - Equip them with new full-flow release valves
 - Gives Factor 8 in discharge cross section
 - Can and will be done *in situ* at cold
- Addition of full-flow release valves on EVERY dipole cryostat (all 1232)
 - Brings overall discharge cross section increase to Factor 40
 - **Can only be done at warm**


Present major activity foreseen in the different sectors	
Sector	Activity
34	Repair of magnets and beam pipes
56	Warmed up for repair of known non-conformity
12	Warmed up for exchange of dipole B16.R1
67	Warmed up for exchange of dipole B32.R6
Others	Kept cold

Restart in 2009


- Installation of ALL protection systems would preclude a run in 2009
 - Install as much as possible in shadow of sector 34 repair
 - Run with reduced risk in 2009
 - Complete installation of new protection systems for 2010
- Restart in 2009 will be determined by
 - Efficiency of logistics of magnets removal / installation
 - Efficiency of magnet repair
 - Efficiency of beam pipe repair / cleaning
 - Efficiency of interconnection activities
 - Time to cool down whichever sectors are warmed up
 - Time to re-commission all power circuits
- Target is beam operation in second half of 2009
 - Lower energy (450GeV to 5TeV)
 - Lower intensity (43 to 156 bunches per beam)
- Push performance in 2010

Prospects

2009



2010



Podziękowania:

L. Evans

R. Saban

R. Bailey

K-H. Mess

K. Dahlerup-Petersen

T. Taylor

L. Rossi